BRUHAT BANGALORE MAHANAGARA PALIKE

Item No. 50

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-TND/04/2011-12 Dated:19.07.2011.

Name of Work: Providing RCC drains at Ramachandrapura Old village in Ward No.10

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of N. Mahesh	
				In Figures	In Words
1	327.10	Removing B.S. slab of Drain and stacking. (P No.24 / i 5.32 SR 2010-11)	Sqm	44.84	Rupees Forty Four and Eighty Four Paise Only
2	111.51	KSRRB 300-1 : Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2m meters and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications complete as per specifications. (P No.126 / i 19.1 SR 2010-11)	Cum	58.88	Rupees Fifty Eight and Eighty Eight Paise Only
3	37.17	KSRRB M300-53: Construction of embankment with approval material Gravel/Murrum with all lifts and leads,transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications. (which includes cost of gravel / murrum, watering charges & compaction by vibratory roller) (P No. 133 / i 19.60 SR 2010-11)	Cum	154.00	Rupees One Hundred Fifty Four Only
4	37.17	KSRB 4-1.3: Providing and laying in position plain cement concrete mix 1:4:8 using 40mm and down size graded granite metal machine, concrete laid in layers not exceeding 15 cms. Thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specification No.KBS 4.1, 4.2 (P No. 12 / i 4.3 SR 2010-11)	Cum	3665.51	Rupees Three Thousand Six Hundred Sixty Five and Fifty One Paise Only
5	743.40	KSRB 4-6.4: Providing and removing centering,shuttering, strutting, propping etc.., and removal of form work for vertical surface such as walls at any thickness,including attached pilasters, buttresses,plinth and string courses cost of all materials,labour complete as per specifications. (P No. 14 / i 4.31 SR 2010-11)	Cum	209.49	Rupees Two Hundred Nine and Forty Nine Paise Only

ಕಾರ್ಯಪಾಲಕ ಇಂಜಿನಿಯರ್
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ,
ಬ್ರ.ಬೆ.ಮ.ಪಾ. ಯಲಹಂಕ ಪಲಯ
ಸಹಕಾರನಗರ, ಬೆಂಗಳೂರು-92.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of N. Mahesh	
				In Figures	In Words
6	74.34	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of mix 1:1.5:3 with 20mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slab, staircase, lintels, retaining walls, walls (any thickness) includingattached pilasters, columns,piers, abutments, pillars,posts,struts, buttresses, string or lacing courses,parapets,coping, bed blocks, anchor blocks plain window cills,fillets etc.., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1, 4.6 (P No. 12 / i 4.11 SR 2010-11)	Cum	**5502.23**	Rupees Five Thousand Five Hundred Two and Twenty Three Paise Only
7	44.60	KSRB 4.9.2 : Providing T.M.T steel reinforcement for RCC work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and westage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. (P No. 16 Item No.4.46 PWD SR 2010-11)	Qntl	**5456.94**	Rupees Five Thousand Four Hundred Fifty Six and Ninety Four Paise Only
8	247.80	Refixing stone slabs of drains and pointing in C.M. (1:3) (P No.24 / i 5.33 SR 2010-11)	Sqm	**53.79**	Rupees Fifty Three and Seventy Nine Paise Only
9	111.51	Leadfor disposalof debris shall be payable at the following rates	Cum		

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92